BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 78

Name of Work:-Providing signage board and name boards in ward no:04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.CHENNAKRISHNA P	
				Rate	Rate in Words
1	Providing and fixing ornamental name boards of size 2.10 X 0.50Mtrs and column of size 0.15 x 0.15 Mtrs of height 1.23 Mtrs of each board made of C C 1:1, 5:3 with necessary centrering and form work smooth finishing with reinforcement etc including fabrication charges painting concreting and transportation charges from manufacturing yard to the site of work all lead and lift loadiing and undloading and labour charges etc. complete as per the direction of the engineer incharge of the work	**Nos**	15.00	6000.00	Rupees six thousand only
2	Retro - Reflectorised Traffic Signs :- **Providing and fixing of retro - reflectorised cautionary, mandatory and informatory sign** as per IRC : 67 - 2001 made of high intensity grade micro prismatic HIP type IV sheeting, fixed over alumium sheeting, 2mm thick firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45cms x 45cm x 60cm, 60cm below ground level as per approved drawing. The **item includes earthwork excavation, Cement Concrete M-15 grade, 2 coats of approved colour synthetic enamel painting** to the steel surface, as per clauses, including curing, cost of all materials, labour, loading, unloading, lead, lift, transporting etc., complete.(P.No.65, I.No.8.04 of NH SR 2009-10) Supported on a class B GI pipe 80mm outer dia, 3.50mtr long 60cm x 60cm square	Sqm	170.00	4750.00	Rupees four thousand seven hundred fifty only
3	KSRRB 300-1. Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 138/ Item No. 19.2/ PWD SR 2014-15	**cum**	4.50	104.00	Rupees one hundred four only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.CHENNAKRISHNA P	
				Rate	Rate in Words
4	KSRRB 4.1:6Providing and laying in position plain cement concrete mix 1:2:4 with cement @240kgs,with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted,in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification no 4.1,4.2 (Page.12 & Item No. 4.6)	**cum**	4.50	4720.00	Rupees four thousand seven hundred twenty only
5	KSRRB M800-9: **Painting new Kannada letter and figures of any shade with synthetic enamel paint block or any other approved** colour to give an even shade complete as per specification, ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) MORTH specification No. 803, No. 192/ Item No. 24.9/ PWD SR 2014-15	**cum**	45060.00	0.60	Paise sixty only
6	**KSRRB M800-6**: Painting two coats on new concrete surface:- Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces complete as per specifications. MORTH specification No. 803, No. 192/ Item No. 24.7/ PWD SR 2014-15	**Sqm**	97.20	60.00	Rupees sixty only
7	**Lead for Disposal of Debris** shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 7.00 Km Average Weight of Earth 1.28 Ton/Cum	**cum**	4.50	79.00	Rupees seventy nine only

P. chanks
Signature of the Contractor

Executive Engineer,
Yelhanka Division,
BEMP, Bengaluru-64.

EE : xxxx ... Engineer Yelhanka Zone